



Worcester County Administration Office
1 West Market Street, Room 1103
Snow Hill, MD 21863
Ph. 410-632-1194

Addendum # 4 - Dugout Replacement Project at John Walter Smith Park *(Additional Questions & Answers)*

Date of Addendum: **July 28, 2026**

NOTICE TO ALL BIDDERS AND PLANHOLDERS

The Bid Documents for the above-referenced Project are modified as set forth in this Addendum. The original Bid Documents and any previously issued addenda remain in full force and effect, except as modified by this Addendum, which is hereby made part of the Bid Documents. Vendors will take this Addendum into consideration when preparing and submitting a bid and shall acknowledge receipt of this Addendum in the space provided in the Bid Documents.

BID SUBMITTAL DEADLINE

The bid submittal time has not been changed.

1.0 – ATTACHMENTS

Item	Description
------	-------------

2.0 – CLARIFICATIONS

The following clarifications are provided as a matter of information to clarify issues raised about the Bid Documents.

Item	Description
------	-------------

3.0 – QUESTIONS AND ANSWERS

The following questions and answers are provided as a matter of information to clarify issues raised about the Bid Documents.

Item	Questions and Answers
1	What gauge wire reinforcing is required for the concrete slabs? 10-gauge wire will be sufficient.
2	Will there be a thickened edge or turn down at the perimeter of the slabs? If so, please provide a detail with any required rebar. No, the edge will remain the same.
3	It appears that there needs to be a thicker detail for supporting the steel posts. The supplier's literature mentions that they use ½" x 8-1/2" concrete wedge anchors. Please provide a cross section or at least a detailed description of this area of concrete. A detailed description is not available at this time. All dugouts should be installed per the manufacturer's recommendations.
4	Will there be a 4" #57 stone base under concrete slab? An adequate base such as 4" of #57 stone is suitable.
5	Will it be required to reestablish grass around the work area or will existing dirt re-spread and compacted be sufficient? Yes, grass seed should be re-established if needed in the work areas.

END OF ADDENDUM