


JWS Dugout Replacement Project Specs

General Scope:

Dugout replacement at John Walter Smith Park in Snow Hill Maryland, on field 5,6, and 7.



Bid Specifications

1. All permits are to be obtained by contractor.
2. Contractor is responsible for demolishing and disposing of existing dugouts and concrete on Field 5,6,7.
3. (6) Dugouts should be installed according to manufactures specifications in existing locations on field 5,6, and 7 at John Walter Smith Park. Dugouts should be purchased through Dugouts USA, model number **ST1020N**. Dugouts should be black powder-coated frames with a green metal roof. **10' by 20'**.
4. New Concrete pads should be installed 4 inches thick, **12' by 24'**, 4000 PSI, broom finish.

5. Dugouts will need to be wrapped with 2" mesh, 9 gauge (.148 core), black thermally coated steel chain link fabric. Fabric should be attached directly to dugout posts using 4" by 4" fence clamps and wrap the entire dugout except for player access on the end closest to the pedestrian access gate and the front of the dugout. A top rail, mid rail and bottom rail should be used in installation of the fabric.
6. Benches to furnish and be installed in each dugout should be (2) Elite dugout benches from Beacon Athletics. Colors should be gray/black.